

TESTING SÝSTEM FOR DECENTRALIZED WASTEWATER TREATMENT IN INDONESIA

by : Elis Hastuti



Directorate of Engineering Development of Human Settlement and Housing General Directorate of Human Settlements Ministry of Public Works and Housing

Decentralized wastewater treatment in

Indon<u>esia</u>



Decrease of open defecation in 2011-2022: ±1,2% per year

(Source: Indonesian Ministry of National Development Planning, 2023, Ministry of Public Works and Housing /PUPR, 2024)







wastewater access

About 9,29% desludging of decentralized wastewater to Fecal SludgeTreatment Plant (FSTP)

- Total 320 plants (in 38 province): 193 plants operated well, 79 plants not operated.
- Total 206 cities have no FTSP

NATIONAL TARGET OF DOMESTIC WASTEWATER INFRASTRUCTURE



LOCAL REGULATION AND WASTEWATER ACCESS



Effluent Standard of Domestic wastewater treatment

INDONESIA



	Province						
Parameter	Jakarta No.122/2005	Middle Java No.5/2012	Yogjakarta No.7/2016	East Java N0.72/2 013	South Sulawesi No.69/201 3	National standard : n	o.68/2016
рН	6-9	6-9	6-9	6-9	6-9	pН	6-9
TSS (mg/L)	50	100	75	50	100	BOD	30 mg/I
$BOD_5 (mg/L)$	50	100	75	30	75	DOD	50 mg/L
COD (mg/L)	80		200	50	100	COD	100 mg/L
Oil Grease(mg/L)	10	10	10	10	5	TSS	30 mg/L
Ammonia (mg/L)	10				5	Oil & grease	5 mg/L
Detergent (mg/L)	2		5		1	Ammonia	10 mg/L
Coliform (MPN/100 ml)			10,000			Total Coliform	3000 /100 mL
` /							

TYPE OF DECENTRALIZED WASTEWATER TECHNOLOGY



BACKGROUND OF TESTING BODY FORMATION IN MINISTRY PUPR FOR EVALUATION OF WASTEWATER TREATMENT PLANT

Organization:

SEJAHTE

-Inspection body in 2012-2019: research institute for human settlement, Bandung city Inspection body in 2020-now: sanitation technology division, Surabaya city (inspector include the old inspection body)

The high demand of prefabricated wastewater tank and have vary quality of material tank and treatment process

Some prefabricated tank often face problems of effluent quality, leaking, tank material inappropriate treatment design/component

Mostly manufactures have no wastewater treatment expert, vary design criteria, regular material test, workshop limitation.

leunyi – 7 Septembe<mark>,</mark> 20

Ministry of Public works and housing /PUPR has responsibility for development, technology guideline/standard availability, training or facilitation of wastewater technology

EXISTING TESTING FOR DECENTRALIZED WASTEWATER PERFORMANCE INSPECTION BODY (certified by national accreditation committee)



EXISTING TESTING FOR DECENTRALIZED WASTEWATER PERFORMANCE

• website http://103.154.122.42/layanan/inspeks

DAFTAR PRODUSEN IPAL TERSERTIFIKASI



DOKUMENTASI INSPEKSI

	Bahan/ Konstruksi	Kapasitas	No. Sertifikat	Tahun	Masa berlaku	Sertifikasi Oleh
	Fiber Reinforced Plastic (FRP)	1 m ³	001/STF/INSPEKSI-BTS/Ch/2022	2022	12 Juli 2022 – 12 Juli 2026	Balai Teknologi Sanitasi
	Polyethylene (PE)	0,8 m ³	002/STF/INSPEKSI-BTS/Ch/2022	2022	19 Agustus 2022 – 19 Agustus 2026	Balai Teknologi Sanitasi
	Fiber Reinforced Plastic (FRP)	50 KK	003/STF/INSPEKSI-BTS/Ch/2022	2022	19 Agustus 2022 – 19 Agustus 2026	Balai Teknologi Sanitasi
	Baja dilapis Fiber Reinforced Plastic (FRP)	80 m³/hari	001/STF/INSPEKSI-BTS/Ch/2021	2021	2 November 2021 - 2 November 2025	Balai Teknologi Sanitasi
	Polyethylene (PE)	12 Orang	002/STF/INSPEKSI-BTS/Ch/2021	2021	15 November 2021 - 15 November 2025	Balai Teknologi Sanitasi
3	Fiber Reinforced Plastic (FRP)	3 x 100 m³/hari	003/STF/INSPEKSI-BTS/Ch/2021	2021	23 Desember 2021 - 23 Desember 2025	Balai Teknologi Sanitasi
	-	50 KK	003/Sert. Uji/PNBP/2020	2020	21 April 2020 – 20 April 2024	Puskim



EFFLUENT QUALITY OF BIOFILTER TANK IN HOUSING AREAS



POTONGAN A - A Skala 1 : 20



Background of national standard for improvement performance evaluation method



ROLE AND OVERVIEW OF THE EXISTING AND RELIABLE

No	Criteria	Existing Testing Method	Expected Testing Method (In the
		(after application product)	laboratory) according to SNI 9161/2023
1	Pra testing	Site preparation:	Pratesting in laboratory max.12 weeks
		Total user according to capacity,	a. Product instalation at laboratory
		operated well, desludging, no	b. Operation by addition sludge artificial
		flood, safe environment, etc.	c. Operation at seeding stage
2	Capacity	Individual tank or communal tank	Individual tank or smallest product
3	Water quality	3-5 days, composite every 3-4	a.Daily monitoring: pH,T,
	sampling	hours (depend on laboratoty	b.Weekly monitoring: min. 10 weeks
	periode	distance)	
4	Wastewater	real wastewater	Real and artificial wastewater
5	Testing at	Sampling at high and normal	Testing at normal, high and low loading
	loading rate	loading rate	rate: minimum 12 weeks
6	sludge	measurement of sludge high at	Performance measurement by artificial
		every process unit	sludge

Real wastewater influent (but try to follow SNI 9163-2023) Problems: -water supply is often limited -existing capacity doesn't match design



Wastewater influent (real & artificial)

	pН	BOD (mg/L)	COD (mg/L)	TSS (mg/L)	NH ₄ -N (mg/L)
Minimum	5,8	150	180	120	10
Average	7,2	200	420	160	27,5
Maximum	8,6	350	550	200	45

ROLE AND OVERVIEW OF THE EXISTING AND RELIABLE TESTING SYSTEM

No	Criteria	Existing Testing Method (after application product)	Expected Testing Method (In the laboratory) according to SNI
7	Tank structure	a.In workshop: dimension, thickness, composition, leaking test, pressure test b.In laboratory : sample material	In laboratory : sample material and test at full scale (leaking test, pressure test, loading test, pit test)
8	certificati on	Valid for 4 years at an inspected product has certain capacity or treatment process. Manufactures have apply often certification for vary capacity	Valid for certain design or treatment process at planned capacity



Test pit in Ministry PUPR

Leaking test in manufacture

FRP Material test in laboratory of Ministry PUPR

Implementation situation for establishment the reliable testing center

Promote reliable testing method according to SNI 2023: to sanitation division, local government, university, research center



The pilot plant of performance testing facility had been developed in Bandung's Water company for standard validation.

The tank structure testing facility and laboratory developed in Ministry of PUPR to support research or special evaluation for some product.

The existing testing body / inspection body have been applying some guideline in SNI 2023, eg. Raw water quality, structural tank test

The manufactures apply testing method for tank structure, such as leaking test, loading test according to SNI 2023













Implementation situation for establishment the reliable testing center

The pilot plant of performance testing facility had been developed in Bandung's Water company for standard validation.

Problems during pilot plant: cleaning rubbish in wastewater collection unit, instrumentation incapable of handling solids, wastewater mixed with rain water, less maintenance of sewer, manual monitoring, competent operator









Challenge for establishment a testing center

The establishment the reliable testing face challenges: vacumm activity during pandemic, ministry reorganization, priority on development basic laboratory and acceleration access of infrastructure

institutions are potential as testing center: Ministry'inpection body, Bandung's water company, Jakarta's wastewater company, university

The collaboration institution, competent human resources (often officials transfer, some will move to new capital city), laboratory facility.

The problem of locations alternative for wastewater source: collection unit, potential contribution of household industry, piping system



Setiabudi' centralized WWTP-Jakarta City (PD. PAL JAYA)

Gumuruh's centralized WWTP- Bandung City (water supply company)



WWTP in Multistorey building, Sumedang City (Bandung Institute of Technology))



WWTP in Multistorey building, Surabaya City (PUPR)

FUTURE SCHEME OF CERTIFICATION SYSTEM



CERTIFIED PRODUCT FOR SANITATION ACCESS PROGRAM

Target

- Increase impoved and safe access
- Contribution in decrease stunting
- Participatry approach for development
- Increase awareness in implementing clean and healty living behaviour (PHBS program)

Program – Infrastructure with community based (IBM)	 Individual, communal-onsite (2-10 HH), communal –offsite (min. capacity 175 people) WWTP for Religious educational institution (min. capacity for 30 students) 	
Program- grant fund for onsite treatment	 Grant funds are incentives or stimulant funds for local governments had funding allocations for waste water 	Selection of conventional or prepabricated tank (biofilter tank)
Program- President Instruction 2024 (155 cities/regency)	 Expansion of offsite system for districts/cities have WWTP with idle capacity Development onsite treatment for districts/cities have fecal sludge treatment plant 	 Land availability (septic tank conventional need large area for infiltration field) Community aggreement Temporary employement creation for community
Program-Spesific allocation Fund (for priority, slum area)	 Development of individual, communal system (5-10 HH); Development communal WWTP min. capacity 50 HH 	 Certified prefabricated tank for area are lack of water for concrete construction, skilled person, less material access

IMPLEMENTATION STRATEGY OF RELIABLE DECENTRALIZED WASTEWATER TESTING

Prevention of environmental degradation (institution and technical aspect)

- Encourage and maintain the commitment of local government or stakeholders in mainstreaming sanitation development in the regions
- Encourage the formation and strengthening of sanitation management institutions in the regions
- Local government conduct routine education of clean and healthy behaviour, community participation, technology standard
- Monitoring of technology application, scheduled desludging
- Convincing good prefabricated wastewater tank that have high performance, low cost instalation, small space, earthquike resistance, etc



In 2024: A total of 119 from 183 (67%) of local government in program socialization had used prefabricated tank



IMPLEMENTATION STRATEGY OF RELIABLE DECENTRALIZED WASTEWATER TESTING

Human resource advancement

- Capacity building in treatment design, application (both conventional/pabrication tank), tank material and structure
- Dissemination of existing inspection and reliable testing method for decentralized wastewater plant to local government, water company, private

Adaptation to national standard

- Multi stakeholder collaboration for testing center, development, guideline draftesting body (scope of work addition of existing inspection body)
- In existing inspection body: adopt some method as condition and encourage manufacture to have facility for pilot tank test
- Planning of wastewater source, human resources, laboratory, maintenance, monitoring
- Encourage for testing center formation or addition new work for existing inpection body, preparation of work instruction/quality guideline document, evaluation method

SEPTIC TANK

THANK YOU FOR YOUR ATTENTION

